



CHASSIS: SPARTAN METRO-STAR EMFD 20" ROOF
 PUMP: HALE RSD 1050 IGPM PTO DRIVE
 TANK: 2000 Imp. Gal. POLYPROPYLENE
 1 - 20 Imp. Gal. FOAM CELL
 FOAM: FOAM PRO 1600

SUCTION: 1 - 6" LEFT (MAN. GATE)
 1 - 6" RIGHT (MAN. GATE)
 1 - 3" TANK TO PUMP (PLUMB 4")
 2 - 2 1/2" RIGHT
 1 - 2 1/2" LEFT

DISCHARGES: 1 - 4" RIGHT
 1 - 3" MONITOR
 2 - 2 1/2" REAR
 1 - 2 1/2" LEFT
 1 - 2 1/2" RIGHT
 1 - 2 1/2" SPEEDLAY

1 - 4" TANK FILL
 1 - 1 1/2" SPEEDLAY

-ALL ALUMINUM CONSTRUCTION - ALL DIMENSIONS ARE IN INCHES & APPROXIMATE

0	FIRST ISSUE	BY	DATE
REV	DESCRIPTION		
REVISIONS			
THE MUNICIPALITY OF LAMBTON SHORES		TITLE GENERAL ARRANGEMENT	
JOB No.	PROPOSAL		
DRAWN BY	T CULLINS		
DATE	05-10-22		
METALFAB LTD. 847 CENTRAL ST. CENTREVILLE NB. CANADA E7K 2E8		DRAWING NO.	FT-11582
		REV	A